Paul. N.K.

3	KSRB 4.2.2 Providing and laying in position reinforced cement concrete of nominal mix 1:1.5:3 with 20mm and down size machine granite metal machine mixed concrete laid in layers not exceeding 15 cms thick vibrated for all works in foundation plinth and ground floor level for roof slabs staircase lintels, retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments pilars, posts struts, buttresses, string or lacing courses parapets, coping, bed blocks, anchor blocks plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery curing complete as per specifications Specification No KSR 4.1.4.5 P.13/4.11									
		Cum								
	Walls		2x1	210.60	0.15	1.00	63.80			
	Bed		1	210.00	0.60	0.15	18.90			
			2x1	142.00	0.15	1.00	42.60			
			1	142.00	0.60	0.15	12.78			
							137.28	5047.92	692978.00	
	Basic Rate	4674.00								
	Area Weightage @	373.92								
	Total	5047.92								
4	KSRB 4.9.2 providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks, and wastage shall not be measured and shall cost of material labour, HOM of machinery complete as per specifications Specification No. KSR 4.9.2 Page No. 19/ Item No. e 46/ PWD SR 2011-12									
		Qtls								
							82.37	6382.80	525738.00	
	Basic Rate	5910.00								
	Area Weightage @	472.80								
	Total	6382.80								
5	KSRB 4.6.4 Providing and removing centering, shuttering, strutting, propping etc and removal of form work for vertical surfaces such as walls at any thickness including attached pilasters buttresses plinth and string courses cost of all materials, labour complete as per specification Specification No. KSR.B 4.6.9 Page No. 17/ Item No. 4.6 PWD SR 2011-12									
		sft								
	Walls		2x2	210.00		1.00	840.00			
			2x2	142.00		1.00	568.00			
							1408.00	555.12	781609.00	
	Basic Rate	514.00								
	Area Weightage @	41.12								
		555.12								

Paul. N. K.